

BRUHATH BENGALURU MAHANAGARA PALIKE
Yolahanka Division, Yolahanka Zone
BBMP/2023-24/OW/WORK_INDENT1083

Executive Engineer
Yolahanka Division
B.B.M.P. Bengaluru - 64

No:EE/YNK-D/E-PMT/05/2023-24 Dated: 13-12-2023

APPROVED TENDER SCHEDULE - B


Item-01

Name of Work:-Removal of silt & Repairs and maintenance of footpaths in ward no-01 Kempegowda.

Sl	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri.SHADAYAN(GANESH ENGINEERING WORKS)	
				Rate	Rate in words
1	Supply of Unskilled Mazdoor Heavy Labours As per orders of minimum wages Act KAE 02 LMW 2015 Dt: 06-01-2017 for emergency works.	Day	2016.00	662.57	Six Hundred SixtyTwo Paise FiftySeven Only
2	Supply of Skilled Mason or Brick layer Class-IAs per orders of minimum wages Act KAE 02 LMW 2015 Dt: 06-01-2017 for emergency works.	Day	288.00	696.83	Six Hundred NinetySix Paise EightyThree Only
3	Providing and laying 100mm thick pre-cast cover slabs over drains & Rain pit of width not exceeding 800 mm using M20 concrete reinforced with Micro Alloyed High carbon steel with 3mm - 3ply wired steel @ 2.00 kg/m ² , slabs jointed in CM 1:3 proportion and nicely finished Including providing holes in the Cover slabs wherever necessary for easy drainage of surface water including of labour, materials, scaffolding, usage of machinery, curing, lead and lift charges etc, Complete.	Sqm	180.00	1051.22	One Thousand FiftyOne Paise TwentyTwo Only
4	Providing and fixing pre cast solid cement concrete kerb stones made out of M20 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting, including formwork, curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc., complete. as directed by the Engineer in Charge of the work.	Nos	139.00	574.32	Five Hundred SeventyFour Paise ThirtyTwo Only
5	Providing and laying 60mm thick factory made cement concrete paverblock of approved shape and colour of M -30 grade made of C&D waste by block making machine with vibratory compaction laid in required pattern and including over 50mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineer-in-charge.	Sqm	179.04	906.22	Nine Hundred Six Paise TwentyTwo Only
6	Lead for disposal of earth shall be payable at Carriage rates (Lead & Lift) by mechanical means including loading and unloading up to 15kms.	Cum	1200.00	227.92	Two Hundred TwentySeven Paise NinetyTwo Only
7	Providing and constructing un-reinforced plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement or any other type as per Clause 1501.2.2 M20 (Grade), coarse and fine aggregates conforming to IS:383:2016, maximum size of coarse aggregate not exceeding 25 mm, mixed in a concrete mixer of not less than 0.2 cum capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate.	Cum	135.00	7220.34	Seven Thousand Two Hundred Twenty Paise ThirtyFour Only
8	Supply of Material component Bitumen (emulsion) Rapid Setting RS1* for all road works. <i>SHADAYAN</i>	t	2.00	48936.10	FourtyEight Thousand Nine Hundred ThirtySix Paise Ten Only

Sl	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri.SHADAYAN(GANESH ENGINEERING WORKS)	
				Rate	Rate in words
9	Supply of Hydraulic Excavator of 0.9 m3 bucket on hire basis including operator, fuel and other incidental charges etc., complete	hr	180.00	1529.25	One Thousand Five Hundred TwentyNine Paise TwentyFive Only
10	Supply of Tipper-5.5 m3 on hire basis including operator, fuel and other incidental charges etc., complete	hr	384.00	1599.49	One Thousand Five Hundred NinetyNine Paise FourtyNine Only
11	Supply of Material component M-Sand - Fine for all road works.	Cum	150.00	1671.98	One Thousand Six Hundred SeventyOne Paise NinetyEight Only
12	Supply of Material component Granular Aggregates of 12mm downsize for all road works.	Cum	100.00	1510.00	One Thousand Five Hundred Ten Only
13	Supply of Material component Granular Aggregates of 20mm downsize for all road works	Cum	100.00	1510.00	One Thousand Five Hundred Ten Only
14	Supply of Material component Granular Aggregates of 40mm downsize for all road works.	Cum	100.00	1348.01	One Thousand Three Hundred FourtyEight Paise One Only
15	Supply of Material component Cement (OPC/PPC/PSC) for all road works.	Nos	450.00	331.90	Three Hundred ThirtyOne Paise Ninety Only
16	Provision for tool - Equipments (Masonry Trowel, Head Pan, Digging Bar, Hammer, Tamper, Hand Gloves, Rubber Boots, etc.,)	LS	1.00	25745.00	TwentyFive Thousand Seven Hundred FourtyFive Only

SHADAYAN
Signature of the Contractor


Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.